

## PRICE BID

**Baroda Apex Academy, Law garden, Ahmedabad**

Sr. No.	Item Description	Quantity	Unit	Rate	Amount (in RS)
1	<b>X-Ray Baggage Scanner</b> - Tunnel Size: 620 mm(W) x 420 mm(H) (±50mm) Product Size: 615*410 mm(width×height) (±50mm) Wire Resolution: Typical AWG36AWG Penetration Resolution: typicalAWG35 Spatial Resolution: Vertical:1.6mm, Horizontal:1.6mm Steel Penetration: Typical 35m (±20mm) X-Ray Dosage for Each Inspection: ≤4.5µSv(uGy) Boundary Leakage: ≤1.0µSv /h(uGy/h) Conveyor Speed: 0.2m/s Conveyor Max Load: 160kg Power Consumption: 1.0 KW Wire Resolution-36AWG, CCTV- 4 built-in Nano Cameras with 4K resolution, 2 on entry side & 2 on exit side. The videos can be viewed through mobile. Linux Operated, 4GB RAM, 2 TB HDD High Resolution of 1024x1280 pixel. Multi Energy, Steel Penetration 35 mm, Resolution 40 AWG, High Image Resolution with 24 Bit Colour, Artificial Intelligence, Box Identification and Buzzer Alarm for Threat items, Picture Perfect Image Analysis, Real Time Diagnostics, Small Footprint with wheels (Portable), Bi Directional	2	Nos		
2	Supply and Installation of <b>Boom Barrier -Up To 6 Mtr.</b> Including High Range Reciver, High Range Remote Control, A Pair Of Photocell Eyes, Push Button, Loop detector, Cabinmate material- Powder coated , Boom Material- Aluminum Alloy.	6	Nos		
3	Supply and Installation of <b>Hand Held Metal Detector Scorpion™ 700139 US STYLE—Classic LOOKS</b> <b>Minimum Dimension- 410 mm X 45 mm X 85 mm</b> <b>Weight - 400 Gms (+- 50 Gms)</b>	10	Nos		
4	Supply and Installation of <b>Hand Held Metal Detector (LED Bar)</b> With super high sensitivity, <b>Minimum Dimension- 410 mm X 45 mm X 85 mm</b> <b>Weight - 400 Gms (+- 50 Gms)</b>	10	Nos		
5	Supply and Installation of <b>Door Frame Metal Detector</b> Inbuilt Control Unit. Working temperature=-5°C to+50°C, Standard External size 2200mm(H)X800mm(W)X580mm(D), Simultaneous alarm from multi Zones, 7" LCD panel Display, automatically count Visitors, High density Fire proof material. Weight < 75 kg	4	Nos		
	<b>Total Amount without GST</b>				
	<b>GST @18%</b>				
	<b>Total Amount with GST*</b>				
	<b>Amount in word incl. GST</b>				

\* The rate quoted by the bidders including all lead lift up to terrace level, tools tackles, wastage, taxes ( excluding GST),cess, duties, transportations, loading unloading up to terrace level (approx.-45 mtrs height).