



BANK OF BARODA

Baroda Pride, 41 Luz Church Road

Mylapore, Chennai -600004

Landline : 044 - 2345 4373

**RECTIFICATION WORKS OF EXISTING WATERPROOFING SYSTEM IN THE
BASEMENT FLOOR OF BARODA PRIDE, OFFICE BUILDING AT MYLAPORE,
CHENNAI**

BILL OF QUANTITIES

VOLUME - III

BILL OF QUANTITIES - WATER PROOFING TREATMENT

BILL OF QUANTITIES - WATER PROOFING TREATMENT					
	Approved list of Makes :	M/s Thermax ,M/S Ardex , Dr Fixit, BASF, M/s SIKA, M/s FOSROC, or Equivalent.			
S.No	Description	Unit	Qty	Rate Rs	Amount Rs
1	Old plaster removal by chipping Hacking of CC Wall surfaces, including clearing any motor and clearing the debris etc. complete as per the direction of Engineer-in-Charge.	Sqm	254.00		-
2	Floor Chipping Chipping & removing the entire old area protection layer, loose mortar and dust particles etc,. And clearing the debris away from site .complete as per the direction of Engineer-in-Charge.	Sqm	146.00		-
3	Drilling of holes at intervals of 0.75m to 1m c/c and along the construction joints and points of leakage, fixing suitable PVC nozzles and injecting PU form with approved chemical and under pressure of around 200 psi, injecting until point of refusal and then plugging the nozzle with quick-setting cement, inclusive of materials, labour, complete.				
a	Walls	No's	285.00		-
b	Flooring	No's	278.00		-
4	Applying approved Crystalline water proofing liquid membrane of two coats at required interval of time over entire area after injection grouting.				
a	Wall + Floors	Sqm	399.00		-
5	Providing 2 Coats of 20 mm thick plaster in wall over the Protective water proofing membrane (overall thickness 40 mm of 2 layers)with C.M 1:4 mixed with approved water proofing chemical as per the required proposition with the manufacture's make.				
a	Wall Plastering	Sqm	254.00		-
6	Providing 1 Coat of 20 mm thick plaster on floor over the Protective water proofing membrane with C.M 1:4 mixed with approved water proofing chemical as per the required proposition with the manufacture's make.				
a	Flooring	Sqm	146.00		-
	TOTAL AMOUNT (exclusive of GST)				-