PRICE BID : INTERIOR FURNISHIG, ELECTRIC, AIRCONDITIONING AND AUDIO VISUAL WORKS OF BANK OF BARODA , ZAID OFFICE - RAJKOT

PART :- 1 FURNITURE WORK

Sr.No.	Description	Unit	Qty.	Rate	Amount
1	**Plain Gypsum False Ceiling (With Colour) as per Design**	SQ.FT	1360		
	P & F suspended false ceiling as per design & shape suggested by using standard company sections [GYP-STEEL R], which includes P & F G. I. Perimeter Channels of size 0.55mm th. Having one flange of 20mm & another flange of with nylon aleeves & screws at 610mm c/c. Then suspending G. I. Intermediate channels of size 45mm, 0.9mm th. with two flangs of 15 mm each from the soffits at 1220 mm c/c with ceiling angle of width 25mm x 10 mm x 0.55mm th. fixed to soffits with G. I. cleats & steel expansion fasteners. Ceiling sections of 0.55mm thickness having knurled web of 51.5mm & two flangs of 26mm. Each with lips of 10.5mm area then fixed to the main intermediate channel with the help of connecting clips & in direction perpendicular to the intermediate channel at 457 mm c/c. 12.5 mm th. tapered edge Gypsum Board (Confirming to I.S.-2095-1982) is then screw fixed to ceiling section with 25mm drywall screws at 230 mm c/c. Screws fixing is done mechanically either with screwdriver or drilling machine with suitable attachment.				
	Standard company manufactured sections [GYPSTEEL R] should be used for the entire framework. Finally the board are to be joined & finished so as to have a finish look which includes filling & finishing the tapered & squarev edges of the boards with joining compound, paper tape & two coats of primer suitable for Gypsum Board (As per recommended practices of India Gypsum or equivalent). **GENERAL NOTES FOR THE ABOVE ITEM RATE INCLUDES:** The job includes applying two or more coats of royale category **'Velvet Touch'** emulsion paint in the standard procedure of painting job. The cut-outs for variety of light fixtures, A.C. continuos grills & diffusers, music speakers & other equipment's etc. & the same have to be made with the frame of perimeter channels of size: 20mm X 27mm X 30mm X 0.55mm thick, supported suitably. **No extra will be paid for this.**				
	The visible area will be considered for the measurement purpose. overlapping & visible vertical drops of the boards will not be cosider for measurement purpose. The trap door made out of 19mm plywood with proper teak wood frame fixed to the structural ceiling & all required hardware such as hinges, locks, stoppers, handles etc comp. in plastic emulsion paint finishes surrounding ceiling finish. [2 Nos.] Angle bead has to be used to at steps to get straight line. Edges bead has to be used to protect the exposed Gypsum core I.E. cut edges of opening for light fixtures, A.C. grills, diffusers, speakers etc. "V" grooves should becut at every square edge joints/filled with joining compound & paper tape.				
2	**False Ceiling (Armstrong)**	SQ.FT	690		
	Providing and fixing in position false ceiling in armstrong 600 x 600 x 15/16 mm Dune Supreme RH 99 Prima tile with **15mm Tegular edge framework with microlok** as specified by Armstrong Co. with suspenders wherever required. Making necessary framework for A.C. ducting, if any and necessary cutouts for diffusers and light fittings, taping and finishing to proper line & level, including making grooves and trap doors for A.C. unit in 18 mm thick M.R. Grade Plywood with Stainless steel hinges & locks with moulding 1" x 1" for edges including finishing with white Plastic Emulsion Paint etc. complete in all respects. (Note: Only the plan area will be measured for payment. No extra payment will be, made for cutouts, grooves, mouldings etc,).				

3	**Laminated Panelling**	SQ.FT	600		
	Providing and laying pannelling on walls & pillers having 12mm th Commercial Plywood of Approved make **(DURO MAK Conforms IS:303 & IS:1659**) and **1.0mm th laminate (Royal Touch laminate as per approved color CW-132 EGG WHITE AND CF-207 FANTA)** fixed on wall & pillers with aluminium framing of 25mm x 25 mm x 1.20 mm thick at maximum 2'-0" c/c bothways or 18 mm thick plywood with laminate panelling on wall and piller and creating box above main door and fixed glass partition etc complete as directed. pannelling as per design and instruction of Architect.				
4	**Partly Glazed Full / Low Height Partition**	SQ.FT	1150		
	Providing and fixing both sides laminate full height partly glazed partition using 50mm x 25mm x 1.50mm thick Aluminium members in a maximum grid of 600mm x 600mm fixing 12mm th Commercial Plywood of Approved make **(DURO MAK Conforms IS:303 & IS:1659)** on both sides with **1.0 mm laminate (Royal Touch laminate as per approved color CW-132 EGG WHITE AND CF-207 FANTA)** shall be fixed on plywood. Providing and fixing 12 mm thick TOUGHNED glass as directed in the partition. Providing and fixing door shutter using 32 mm thick flush shutter both side laminated and fixing 8.0 mm thick glass with beading patti, 5" Long 3 Nos stainless steel hinges, doorstop shall be provided as directed. **Ozone Knob Lock (OCKL-11N-70MM STD SSS)** shall be provided in door shutter. All visible members if not laminated shall have lacquer polished as directed. The partition shall be secured by fixing & extending the vertical members of the frame at critical points upto the bottom of the RCC Slab or sides/bottom of RCC beams & bottom horizontal member of frame shall be secured & fixed with the flooring as directed. Providing and fixing aprox 6 mm thick white /pattern colour Monteli **(Dupont corian)** material (of basic rate or above of Rs. 750 / sq.ft._ instead of Laminate on partition. as above in approved pattern as per drawing. Providing and fixing aprox 18 mm thick white /pattern colour birch ply as approved by architect instead of Laminate on partition. as above in approved pattern as per drawing. **For purpose of payment partition height up to bottom of false ceilling only shall be measured and paid . No extra payment shall be made for members going up to slab/beam bottom.**				
5	**Pantry Platform Shutters including SS Basket (6Nos)**	SQ.FT	25		
	Providing and fixing Loft shutters / Pantry Platform shutter to be made out of 2"x1" teak wood frame, 18mm thk. waterproof Ply **(DURO MARINE Conforms to IS 710)**, T.W. beading finished with melamine polish , both side 1 mm thk. laminate **(Royal Touch laminate as per approved color CW-132 EGG WHITE AND CF-207 FANTA)** incl. all necessary hardware fittings, 6nos basket and locking system as suggested area. as per list of approved material, instruction and design of architect / bank including all labour and materials insluding 6NOS basket.				
6	**ROLLER BLINDS**	SQ.FT	325		
	Install sunscreen roller blind with same fabric palment of **VISTA BRAND** as per specification, Approved fabric sample from the Architect with **printing on fabric as per bank selected graphics.** Measurement will be taken as per actual size of window on site, there are no any other measurement will consider over window size.				
7	**Soft Board:-**	SQ.FT	75		
	Providing and fixing of Soft board made out of 19mm, 12mm com. Plywood **(DURO MAK Conforms IS:303 & IS:1659)** framing. The back shall be in 6mm thk. come. Plywood **(DURO MAK Conforms IS:303 & IS:1659)** with cotton cloth fixed over 1/2" thk. celotex board. All exposed ply. surfaces are finished in 1 mm thk. laminate **(Royal Touch laminate as per approved color CW-132 EGG WHITE AND CF-207 FANTA)** of approved shade & make and beading in Melamine finish all complete as per design and instruction of the Architect with all labours and materials.				

8	**DGM TABLE (SIZE :- 6'6"X3'0"X2'6")**	NOS	1		
	Supplying and providing table as per following description ,table top shall be made with 36 mm thick composite white glass marble **(KALINGA STONE - STELLAR WHITE)** with all exposed edges of top with another 18 mm thick composite marble to show front thickness 36 mm thick edges. In front of table made of 18mm thick plywood **(DURO MAK Conforms IS:303 & IS:1659)** cover with 1"x0l T.W bidding finish with Melamine finish as complete per design and insturction of architect with all labours and material. Drawers unit of 1'9"D x 1'4" W x2' 6" H shall be provided by using 18 mm thick plywood **(DURO MAK Conforms IS:303 & IS:1659)** having 4 nos. drawers (as shown in dwg.) of with heavy duty telescoping sliding channel of **Ebco make**, ebco side lock with **Enox handle profile (EAPS-034)**. Cable organizer & cable box as per drawing shall be fixed in position. all complete as per drawing and direction by Architect and incharge. Boxing Made of 18 Mm thick plywood **(DURO MAK Conforms IS:303 & IS:1659)** below the table top for electrical coduting & at the bottom for the LAN cabling/ telephone wiring. all non visible surface should be 1 mm thick laminate **(Royal Touch laminate as per approved color CW-132 EGG WHITE AND CF-207 FANTA)** Providing and fixing aprox **6 mm thick white /pattern colour Monteli corian (DUPONT)** material (of basic rate or above of Rs. 750 / sq.ft._ instead of Laminate on front and side of table. as above in approved pattern as per drawing. complete as per dwg. and instruction.				
9	**AGM TABLE (SIZE :- 5'6"X3'0"X2'6")**	NOS	1		
	Supplying and providing table as per following description ,table top shall be made with 36 mm thick composite white glass marble **(KALINGA STONE - STELLAR WHITE)** with all exposed edges of top with another 18 mm thick composite marble to show front thickness 36 mm thick edges. In front of table made of 18mm thick plywood **(DURO MAK Conforms IS:303 & IS:1659)** cover with 1"x0l T.W bidding finish with Melamine finish as complete per design and insturction of architect with all labours and material. Drawers unit of 1'9"D x 1'4" W x2' 6" H shall be provided by using 18 mm thick plywood **(DURO MAK Conforms IS:303 & IS:1659)** having 4 nos. drawers (as shown in dwg.) of with heavy duty telescoping sliding channel of **Ebco make**, ebco side lock with **Enox handle profile (EAPS-034)**. Cable organizer & cable box as per drawing shall be fixed in position. all complete as per drawing and direction by Architect and incharge. Boxing Made of 18 Mm thick plywood **(DURO MAK Conforms IS:303 & IS:1659)** below the table top for electrical coduting & at the bottom for the LAN cabling/ telephone wiring. all non visible surface should be 1 mm thick laminate **(Royal Touch laminate as per approved color CW-132 EGG WHITE AND CF-207 FANTA)** Providing and fixing aprox **6 mm thick white /pattern colour Monteli corian (DUPONT)** material (of basic rate or above of Rs. 750 / sq.ft._ instead of Laminate on front and side of table. as above in approved pattern as per drawing. complete as per dwg. and instruction.				

10	**SDO TABLE (SIZE :- 5'6"X3'0"X2'6")**	NOS	1		
	Supplying and providing as per following description, top of this table shall be made up of 18mm + 12mm thick plywood (DURO MAK Conforms IS:303 & IS:1659), covered with 3+3" belt 6mm thick **Monteli corian (DUPONT)** material and laminate as shown in dwg. In front of table made of 18mm thick plywood **(DURO MAK Conforms IS:303 & IS:1659)** cover with 1"x0l T.W bidding finish with Melamine finish as complete per design and insturction of architect with all labours and material. Drawers unit of 1'9"D x 1'4" W x2' 6" H shall be provided by using 18 mm thick plywood **(DURO MAK Conforms IS:303 & IS:1659)** having 4 nos. drawers (as shown in dwg.) of with heavy duty telescoping sliding channel of **Ebco make**, ebco side lock with **Enox handle profile (EAPS-034)**. Cable organizer & cable box as per drawing shall be fixed in position. all complete as per drawing and direction by Architect and incharge. Boxing Made of 18 Mm thick plywood **(DURO MAK Conforms IS:303 & IS:1659)** below the table top for electrical coduting & at the bottom for the LAN cabling/ telephone wiring. all non visible surface should be 1 mm thick laminate **(Royal Touch laminate as per approved color CW-132 EGG WHITE AND CF-207 FANTA)** Providing and fixing aprox **6 mm thick white /pattern colour Monteli corian (DUPONT)** material (of basic rate or above of Rs. 750 / sq.ft._ instead of Laminate on front and side of table. as above in approved pattern as per drawing. complete as per dwg. and instruction.				
11	**Full / Low Height Storage / Back Storage (Credenza) [A] 16" & 18" deep**	SQ.FT	575		
	Providing and fixing in position Full Height Storage/Low Height Storage/Back Storage (Credenza) as shown in Drg. respectively using plywood of 18MM thickness **(DURO MAK Conforms IS:303 & IS:1659)** finished with 1mm thick laminates **(Royal Touch laminate as per approved color CW-132 EGG WHITE AND CF-207 FANTA).** as shown in the drawing and all non visible sides shall be finished with white laminates as detailed therein. The Storage Units shall be provided with **Enox handle profile (EAPS-034)** as per approval of the project Consultant / Bank. All exposed plywood surfaces to be finished with 1mm thk. laminate **(Royal Touch laminate as per approved color CW-132 EGG WHITE AND CF-207 FANTA).** and all exposed edges of plywood to have 1" x 1/4" T.W. lipping. All exposed T.W. sections to be melamined in matching colot laminates and internal surfaces to have white laminates as directed. The item to include all necessary hardware and fitting in Stainless Steel finish, **EBCO 32MM MULTI LOCK** including magnetic ball catcher and **Soft Close ENOX Auto Closing Hinge (EAH - CL - 011)** etc. complete in all respects. [A] 16" & 18" deep				

12	**Profile Shutter Storage [A] 16" & 18" deep**	SQ.FT	170		
	Providing and fixing in position Full Height Storage/Low Height Storage/Back Storage (Credenza) as shown in Drg. respectively using plywood of 18MM thickness **(DURO MAK Conforms IS:303 & IS:1659)** finished with 1mm thick laminates **(Royal Touch laminate as per approved color CW-132 EGG WHITE AND CF-207 FANTA).** as shown in the drawing and all non visible sides shall be finished with white laminates as detailed therein. Glass Sutter of Storage as shown in Drg. respectively using **Enox Frame Profile (EAPS-005)** and **Enox Handle Profile (EAPS-014)** and 6mm back painted glass of **saint gobbain** as per approval of the project Consultant / Bank. All exposed plywood surfaces to be finished with 1mm thk. laminate **(Royal Touch laminate as per approved color CW-132 EGG WHITE AND CF-207 FANTA)** and all exposed edges of plywood to have 1" x 1/4" T.W. lipping. All exposed T.W. sections to be melamined in matching colot laminates and internal surfaces to have white laminates as directed. The item to include all necessary hardware and fitting in Stainless Steel finish, **EBCO 32MM MULTI LOCK** including magnetic ball catcher and **Soft Close ENOX Auto Closing Hinge (EAH - CL - 011)** etc. complete in all respects. [A] 16" & 18" deep				
13	**FULLY GLAZED FIX GLASS AND DOOR**	SQ.FT	370		
	Providing and Fixing 12mm toughened clear fix glass and door shutter to be fixed as per drawing including approved OZONE S.S. Handle, OZONE hardware and OZONE floor spring **(FS-8400 STD-SSS)**. OZONE lock **(OZ-MGL-11S)** complete as per drawing & instructions.				
14	**FLUSH DOOR SHUTTER [PARTLY GLAZED AND LAMINATE WITH DOOR FRAME WITH LAMINATED PLY WOOD (KOPRA)]**	SQ.FT	50		
	Providing and fixing Flush door shutter made out of 35 mm thick flush door (IS:2202, Part-A). With 35 X 12 mm thick steam beach periphery patti around shutter edges,1 mm thick laminate **(Royal Touch laminate as per approved color CW-132 EGG WHITE AND CF-207 FANTA).** on both sides including 4 Nos. 6" long SS hinges with countersunk SS screws, KNOB Lock, Door consile stoppers and Wooden Consile Handle as per drawing and,all exposed wooden members not laminated be provided with lacquer polish complete as per drawing & instructions.				
15	**LAMINATE CHANGES IN FLUSH DOOR SHUTTER WITH DOOR FRAME WITH LAMINATED PLY WOOD (KOPRA) [SOLID]**	SQ.FT	220		
	Providing and fixing 1mm thick laminate on existing Flush door shutter which is made out of 35 mm thick flush door (IS:2202, Part-A). With 35 X 12 mm thick steam beach periphery patti around shutter edges,1 mm thick laminate **(Royal Touch laminate as per approved color CW-132 EGG WHITE AND CF-207 FANTA).** on both sides including 4 Nos. 6" long SS hinges with countersunk SS screws, KNOB Lock, Door consile stoppers and Wooden Consile Handle as per drawing and,all exposed wooden members not laminated be provided with lacquer polish complete as per drawing & instructions.				
16	**FROSTED GLASS FILM**	SQ.FT	200		
	Providing and Fixing Frosted polyster film of **3M (Scotchcal 7725 - 324)** or equivalent make over glass surface as per drawing & direction with all labour & materials and printing to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will be made for any cutting in the film.				

17	**PLYWOOD BOXING FOR PALMET**	R.FT	60		
	Providing and fixing 9"x9" plywood box made out of 18mm thick plywood **(DURO MAK Conforms IS:303 & IS:1659)** finished with 1mm thick laminate **(Royal Touch laminate as per approved color CW-132 EGG WHITE AND CF-207 FANTA)**. as per design.				
18	**CONFERENCE TABLE**	NOS	1		
	Supplying and providing as per following description, top of this table shall be made up of 18mm + 12mm thick plywood **(DURO MAK Conforms IS:303 & IS:1659)**, covered with 3+3" belt **6mm thick Monteli corian (DUPONT)** material and laminate as shown in dwg. supported by 3 side with intermediate support of 18 mm thick plywood all edges. Front edge should be 36mm thick applying 12mm plywood as per dwg. All visible surface shall be covered by 1.0 mm thick laminate **(Royal Touch laminate as per approved color CW-132 EGG WHITE AND CF-207 FANTA).** Cable organizer shall be fixed in position. Boxing Made of 12 MM thick plywood **(DURO MAK Conforms IS:303 & IS:1659)** below the table top for electrical coduting & at the bottom for the LAN cabling/ telephone wiring. All non visible surface should be 0.8mm thick laminate of approved make all as per direction and dwg. completein all respects including crystal clear table top **12mm toughned glass** with side edge polished.				
19	**WORK STATION**	R.FT	70		
	Providing and fixing in position Work Station Table of size as per drawing by using 36mm thick plywood **(DURO MAK Conforms IS:303 & IS:1659)** for top covered with **3+3" belt 6mm thick Monteli corian (DUPONT)** material and laminate as shown in dwg and 18mm thick plywood **(DURO MAK Conforms IS:303 & IS:1659)** for all other horizontal and vertical members finish with 1.0mm thick laminate **(Royal Touch laminate as per approved color CW-132 EGG WHITE AND CF-207 FANTA)**. Telescopic keyboard trey shall be provide made of 18mm thick plywood **(DURO MAK Conforms IS:303 & IS:1659)** and covered with 1mm thick laminate **(Royal Touch laminate as per approved color CW-132 EGG WHITE AND CF-207 FANTA)** Footrest made with 18mm thick plywood finished with 1mm thick laminate **(Royal Touch laminate as per approved color CW-132 EGG WHITE AND CF-207 FANTA)** and table shall be finished with 1mm thick laminates **(Royal Touch laminate as per approved color CW-132 EGG WHITE AND CF-207 FANTA)** as shown in the drawing and all other non visible sides shall be finished with white laminates & shall be providing with handles (Stainless Steel finish) and channels as per approval of the project Consultant / Bank. Drawers unit of 1'9"D x 1'4" W x2' 6" H shall be provided by using 18 mm thick plywood **(DURO MAK Conforms IS:303 & IS:1659)** having 4 nos. drawers (as shown in dwg.) of with heavy duty telescoping sliding channel of **Ebco make**, ebco side lock with **Enox handle profile (EAPS-034).** All exposed plywood surface to be finished with 1mm thick laminate of approved make & shade as per Bank's norms, and all exposed edges of table top & ply verticals to have 1" x 1/4" T.W. lipping. All exposed T.W. sections to be melamined and internal surfaces to have 1mm thick laminate as approved color as directed. Item to include plywood boxing, all necessary hardware and fitting in Stainless Steel finish, lipping to all edges etc. complete in all respects including crystal clear table top **12mm toughned glass** with side edge polished.				

20	**SOFA**	R.FT	26		
	Supplying and providing SOFA as per the drawing and following description. Clear depth of seat 22" at 16" height, with patty spring at bottom side at about 50 mm distance for support of seat U-Foam first layer of kinny foam of 8mm thick , overall height of back 2'8" skeleton of the sofa shall be made of 18 mm thick plywood (back of back & other face / side of arm rests of 6 to 18 mm ply as per design and covered with U-foam and fabric & bottom of seat hollow) & TW support members of required size and supported on S.S. legs Seat & back shall be padded with 4" th. (40 density) & 2" th. (32 density) sleepwell foam respectively and further covered with 20 mm thick U-FOAM (32 density) & rest of the area to be upholstered shall be covered with 12/ 20 mm density u-foam. it shall be further covered with with white hessian cloth / matherpat all over and upholstered with rexin / cloth (basic rate of the cloth shall be Rs. 650/-Rmt) all over except bottom of the seat in shape & design as per drawing & instructions. complete.				
21	**Wall painting**	SQ.FT	1500		
	Supplying, providing and applying internal wall painting (three coats or more coat required clear finish coat) with royale category **'Velvet Touch'** paint of Asian make after and above also with applying two coat of Birla or Asian acrylic Lappy (putty) and two coats of primar of asian make on undecorated wall/ ceiling surface to give an even shade including thorughly brushing the surface free from mortar dropping and other foreign matter all complete as per company specification and sand papered smooth etc. at any height & direction.				
22	**BANK LOGO :-**	NOS	6		
	Providing & Fixing Bank Logo Or Signage made from 12mm thick acrylic Font with C.N.C. cutting and coloured (as approved by ARCHITECT / Bank) Name plate Size (900mm x 900 mm). The rates are inclusive of all materials, labours and fixing etc. complte				
23	**ELECTRIC BELT**	R.FT	70		
	Providing and fixing 3"x6" plywood box made out of 18 or 12 mm thick plywood finished with 1mm thick laminate as per design.				
24	**12MM GLASS SELF**	SQ.FT	40		
	Providing and fixing 12mm toughned glass self with all materials, labours and fixing etc. complete,				
25	**ARTIFICIAL FLOWER POT 4' HEIGHT**	NOS	8		
	Providing and fixing artifical flower pot with 4'height flower with 1'6"x1'6" artificial pot with all required accessories.				
26	**AUTOMATIC ROOM FRESHNERS**	NOS	8		
	Providing and fixing Godrej aer matic kit (Machine + 1 Refill) - Automatic room freshners with flexi control spray with 2200 sprays guaranteed.				
				TOTAL OF PART 1:-	

PART :- 2 ELECTRIC WORK

Sr.No.	Description	Unit	Qty.	Rate	Amount
1	Supply, installation, testing and commissioning of following point wiring as per the specifications and drawings. The unit rate for the switch board and further to point outlet including all hardware, connector strips, fan hook, outlet boxes, switch boards, switch plates, switches, wire conduits etc. A point shall include in addition to phase and neutral wire, a PVC insulated earthcontinuing wire from L. P. to the final termination at outlet points. All the wiring should be done in concealed / semi concealed open manner or slab / wall / false ceiling. The wiring should be done with rigid PVC conduits / Casing - capping having minimum of 1.6 mm wall thickness and minimum 19mm dia with 440V grade PVC insulated. ISI approved copper conductor wire, with LEGRAND make switches and accessories with company boxes for point outlet and SB and with all required hardware accessories to complete the wiring. No junction boxes are allowed any where in the wiring.				
	All joints shall be done at point outlet on switch boards only. In between joints are not allowed anywhere. The wiring shall be done as per IS 732 and IS 4648.				
	a) Making Zari in the wall & sami finishing the surface.				
	b) Ball and socket joint wherever required.				
	c) Earthing of fittings				
	d) Electrical connections from the outlet points to the fixture with 3 core flexible wire.				
	RATE ARE INCLUDING MAINS CIRUITS				
1.1	**One Light Point Controlled By One 5 Amp. Switch**	NOS	40		
	A) Wire Size: Lighting DB to Switch Board Circuit: Phase Wire -Red/Yellow/Blue Color -2.5. sq. mm-1 no. Neutral Wire -Black Color -2.5. sq. mm-1 no. Earth Wire -Green Color -1.5. sq. mm-1 no.				
	B) Wire Size: Switch to Light Point Circuit: Phase Wire -Red/Yellow/Blue Color -1.5. sq. mm-1 no. Neutral Wire -Black Color -1.5. sq. mm-1 no. Earth Wire -Green Color -1.0. sq. mm-1 no.				
	C) FRLS Wire : Finolex				
	D) Modular Switch : Legrand (Mylink)				
	E) PVC Conduit & Accessories Make : Polycab				
1.2	**Two Light Points Controlled By One 5 Amp. Switch (All Two Light Points are Invertor Points)**	NOS	24		
	A) Wire Size: Light Point to Light Point Circuit: Phase Wire - Red/Yellow/Blue Color -1.5. sq. mm-1 no. Neutral Wire - Black Color -1.5. sq. mm-1 no. Earth Wire - Green Color -1.0. sq. mm-1 no.				
	B) FRLS Wire: Finolex				
	C) Modular Switch: Legrand (Mylink)				
	D) PVC Conduit & Accessories Make : Polycab				
1.3	**One 5 Amp. Switch & Socket Controlled For Wall / EXHUST Fan Point (All Wall Fan Points are Invertor Points)**	NOS	14		
	A) Wire Size: Light Point to Light Point Circuit: Phase Wire - Red/Yellow/Blue Color -1.5. sq. mm-1 no. Neutral Wire - Black Color -1.5. sq. mm-1 no. Earth Wire - Green Color -1.0. sq. mm-1 no.				
	B) FRLS Wire: Finolex				
	C) Modular Switch : Legrand (Mylink)				

	D) PVC Conduit & Accessories Make : Polycab				
1.4	**One 5 Amp. 5 Pin Socket Outlet Controlled By One 5 Amp. Switch Looped On Switch Board**	NOS	18		
	A) Wire Size: Loop Circuit: Phase Wire - Red/Yellow/Blue Color -1.5. sq. mm-1 no. Neutral Wire - Black Color -1.5. sq. mm-1 no. Earth Wire - Green Color -1.0. sq. mm-1 no.				
	B) FRLS Wire: Finolex				
	C) Modular Switch : Legrand (Mylink)				
	D) PVC Conduit & Accessories Make : Polycab				
1.5	**Three 5 Amp. 5 Pin Socket Outlet Controlled By One 15 Amp. At Other Convenient Location For Computer. (Maximum 4 Nos. Of Boards In One UPS Circuit):-**	NOS	30		
	A) Wire Size: UPS DB to Switch Board Circuit: Phase Wire -Red/Yellow/Blue Color -2.5. sq. mm-1 no. Neutral Wire - Black Color -2.5. sq. mm-1 no. Earth Wire -Green Color -1.5. sq. mm-1 no.				
	B) Wire Size: Switch to Socket Point Circuit: Phase Wire - Red/Yellow/Blue Color -1.5. sq. mm-1 no. Neutral Wire - Black Color -1.5. sq. mm-1 no. Earth Wire - Green Color -1.0. sq. mm-1 no.				
	C) FRLS Wire: Finolex				
	D) Modular Switch : Legrand (Mylink)				
	E) PVC Conduit & Accessories Make : Polycab				
1.6	**Two 5 Amp. 5 Pin Socket Outlet Controlled By One 15 Amp. At Other Convenient Location For RAW POWER. (Maximum 4 Nos. Of Boards In One UPS Circuit):-**	NOS	26		
	A) Wire Size: UPS DB to Switch Board Circuit: Phase Wire - Red/Yellow/Blue Color -2.5. sq. mm-1 no. Neutral Wire - Black Color -2.5. sq. mm-1 no. Earth Wire - Green Color -1.5. sq. mm-1 no.				
	B) Wire Size: Switch to Socket Point Circuit: Phase Wire - Red/Yellow/Blue Color -1.5. sq. mm-1 no. Neutral Wire - Black Color -1.5. sq. mm-1 no. Earth Wire - Green Color -1.0. sq. mm-1 no.				
	C) FRLS Wire: Finolex				
	D) Modular Switch : Legrand (Mylink)				
	E) PVC Conduit & Accessories Make : Polycab				
1.7	**One Buzzer Point Controlled By One Bell Push, With Electric Type Buzzer**	NOS	3		
	A) Wire Size: Switch to Buzzer Point Circuit: Phase Wire - Red/Yellow/Blue Color -1.5. sq. mm-1 no. Neutral Wire - Black Color -1.5. sq. mm-1 no. Earth Wire - Green Color -1.0. sq. mm-1 no.				
	B) FRLS Wire: Finolex				
	C) Modular Switch : Legrand (Mylink)				
	D) PVC Conduit & Accessories Make : Polycab				
1.8	**One 15 Amp 6 Pin Socket Outlet Controlled By One 15 Amp. Switch With Indicator (For Router/Printer /Appliance etc.) (Separate And Independent Circuit Required)**	NOS	4		
	A) Wire Size: Lighting/Power DB to Switch Board Circuit: Phase Wire - Red/Yellow/Blue Color -2.5. sq. mm-1 no. Neutral Wire - Black Color -2.5. sq. mm-1 no. Earth Wire - Green Color -1.5. sq. mm-1 no.				
	B) FRLS Wire: Finolex				
	C) Modular Switch : Legrand (Mylink)				
	D) PVC Conduit & Accessories Make : Polycab				

1.9	**One 20 Amp. 6 Pin Socket Outlet Controlled By One 20 Amp. Switch Or 20 Amp. SP MCB With Socket For A. C. Unit. (If Circuit Wire Connected Direct And Without Switch/Socket/MCB To Outdoor AC Unit- 50% Quoted Tender Rate Will Be Paid)**	NOS	9		
	A) Wire Size: AC/Power DB to AC Point Circuit: Phase Wire - Red/Yellow/Blue Color -4.0 sq. mm-1 no. Neutral Wire - Black Color -4.0 sq. mm-1 no. Earth Wire - Green Color -1.5. sq. mm-1 no.				
	B) FRLS Wire: Finolex				
	C) Modular Switch : Legrand (Mylink)				
	D) PVC Conduit & Accessories Make : Polycab				
1.10	**One 5 Amp. Switch & Socket Controlled For CEILING Fan Point**	NOS	1		
	A) Wire Size: Light Point to Light Point Circuit: Phase Wire - Red/Yellow/Blue Color -1.5. sq. mm-1 no. Neutral Wire - Black Color -1.5. sq. mm-1 no. Earth Wire - Green Color -1.0. sq. mm-1 no.				
	B) FRLS Wire: Finolex				
	C) Modular Switch : Legrand (Mylink)				
	D) PVC Conduit & Accessories Make : Polycab				
	E) Hum free EME four or more step type electronic fan regulator :- Legrand (Mylink)				
1.11	**GLOWSIGN BOARD POINT**	NOS	1		
	20 Amp power point for Glowsign board with L & T time switch & with 20 Amp. SP MCB with 4.0 sq. mm. with 2.5 sq. mm. earth wire single phase 3 wire. Including glow signboard timer.				
2.0	**Cables & Cable Terminations**				
	Supplying & laying PVC armoured cable of 1100 V grade of copper / conductor (as specified) of following sizes in ready made trench mounted on wall with necessary clamping arrangement or in prelaid RCC hume pipe with necessary cable identification lugs at both ends, digging of trench and its filing with second call bricks, send. The cable shall ISI mark and conforming to latest ISS. All the cable shall be terminated with suitable sizes of Lugs.				
2.1	4C X 6 sq mm Copper Flexible cable ((Main Panel to Input UPS DB)	MTRS	20		
	FRLS Wire : Finolex.				
2.2	3.5C X 50 sq mm Aluminium armoured cable (Main Cable Meter to Main Panel)	MTRS	130		
	FRLS Wire : Finolex.				

3.0	**Earthing**				
3.1	Safe earthing electrode certified for use upto 11kv with 3.00 m pipe back filling comound 2 bag of 25 Kg. with outer pipe 50mm dia and inner 25 mm dia pipe and compund filling as per UL 476 as approved by PWD (Chemical Copper Earthing) ETP MAKE or ASHLOK MAKE With 3 years Manufacturer warranty.Any other make will not be consider. 3 years Manufacturer Warranty. Earthing Certificate Need to Attached. **(At the Time of buried of earthing Photograph must be taken Without Photographic Proof Earthing Will be Rejected. Earthing Road Photo Must be attached with Bill.)**	NOS	2		
	A) Chemical Copper Earthing :- ETP MAKE or ASHLOK MAKE				
3.2	8SWG CU. Wire with 20 mm dia. PVC rigid conduit duly cleated / concealed / burried in floor etc. complete	R.MT	60		

4.0	**Fixtures & Fittings**				
	Supply, Installation, testing and commissioning of the following luminaries, fixtures and fittings. The fixtures shall be installed on wall, false ceiling etc. and as per the manufacturer instructions. The job also includes the connection of the fixture with outlet point using 3 core flexible wire wherever the lighting fixtures are there. (Earthing of Light Fixture is must). **Led fitting & LED Driver both must be of same make only. The marking & cutting of fixtures should be in ele. contractor's scope..**				
4.1	**11 W LED Down light**	NOS	32		
	A) Energy Efficient round recessed mounted LED down lighter with premium white powder coating and die cast aluminium housing. as per details above. with minimum 2 years warranty.should be connected to supply wire with PVC connector. Earthing connection with lugging need to given to body of Fixture				
	B) Down light : PHILIPS (GreenPerform Sleek - DN296B LED12S-3000 PSU WH)				
4.2	**18 / 20W led batten light fixture (T-5)**	NOS	3		
	A) Supply and instalation of 13 / 20W led batten light fixture (T-5) with electronic driver and tube complete with necessory hardwares, etc and 6000K per watt lumens output must be above 90 lumen/watt and 90%lumems maintaiance for 90% of life with input voltage 90-270v ac 50hz operational without affecting the life, input mov.gtd protection in driver for above 270v protection. and 2 years waranty.LED Batten Comprises of Thermally conductive material. Pre-wired with high efficiency electronic driver. High translucent frosted diffuser gets glare free, smooth light distribution				
	B) LED T-5 Type Patti type : PHILIPS (BN058C LED11/CW L1200)				
4.3	**Wall Fan 16" dia. Blade arrangement**	NOS	9		
	A) Supply and installation of 400 mm sweep wall mounted fan with metal stand and housing guard. **With on site 2 years warranty.**				
	B) WALL FAN : CROMPTON				
4.4	**CEILING Fan 48'' dia. Blade arrangement**	NOS	1		
	A) Supply and instalation of 48" Ceiling Fan with fan step modular regulator, Max. 3 feet Fan Rode, Anchor Fastner, etc.(WHITE COLOUR) approved make ceiling fan, Aluminium body, copper winding.				
	B) CEILING FAN : CROMPTON (Surebreeze Alphabriz 1 Star)				
4.5	**300MM DIA EXHUST FAN**	NOS	5		
	A) Supply and installation of Exhaust fan of 300 mm, fresh air vantilator type with louver complete & 6 Amp. 3 pin TOP. [Wooden mounting frame should be fixed in coordination with carpenter - furniture contractor.]				
	B) EXHUST FAN : CROMPTON (Axial Air)				
4.6	**1 x 18 W LED BULB**	NOS	4		
	A) Supply and installation 1 x 18 W LED BULB				
	B) LED BULB : CROMPTON				

4.7	**25 W LED, Lighting fixture panel suitable for 2'x2' (600mm X 600 mm) Grid/ Gypsum/ POP / Armstrong flase ceiling**	NOS	21		
	A) Supply and installation of 25 W LED, Lighting fixture panel suitable for 2'x2' (600mm X 600 mm) Grid/ Gypsum/ POP / Armstrong flase ceiling of Philips Model Full Glow G6 Cat Ref No: RC380B LED36S-4000 G6 L60W60 PSU OD S1, CCT 4000 K and CRI > 80, lumen O/P > 3300 lumen, Syatem wattage (LED + Driver) < 40 Watt. with minimum 2 years warranty Should be clamp with hook in ceiling. and should be connected to supply wire with PVC connector. Earthing connection with lugging need to given to body of Fixture.				
	B) 25 W LED PANEL LIGHT : PHILIPS (RC380B LED36S-4000 G6 L60W60 PSU OD S1)				
4.8	**FLEXIBLE LED STRIP LIGHT**	R.MT	20		
	A) Supply and instalation of flexible LED strip light complete with driver unit, 230 v, 50 Hz, as required				
	LED Strip Light :- PHILIPS				
5.0	**Panel Board/Distribution Boards**				
5.1	**Supplying and erecting complete with 14/ 16 SWG complete floor / wall mountain type with required compartment including meters & lamps with following materials**	NOS	1		
	A) S. F. U. (HRC type) 160 A TPN - 1no.				
	B) 63 COS - 1no.				
	C) 63A FP MCB - 3no.				
	D) 40 A DP MCB - 2no.				
	E) Digital A meter V meter & F meter with selector switch R Y B LED Lamp with indicator and required cable glands etc.				
	F) Switchgear & MCB Make : Legrand				
	G) AVF Meter Make : TRINITY				
5.2	**Supplying and installing, testing and commissioning of DB with following ; (for lighting Purpose and Invertor Purpose)**	NOS	2		
	A) Incoming : 40 A DP EL + MCB - 1no.				
	B) Outgoing : 16/10/25 Amp SP MCB - 8nos.				
	C) MCB & DB Make : Legrand				
5.3	**Supplying, installing, testing & commission of Distribution Board with following : (for A. C. units)**	NOS	1		
	A) Incoming : 63 A FP MCB - 2no.				
	B) Outgoing : 25 A DP MCB - 10nos.				
	C) MCB & DB Make : Legrand				
5.4	**Supplying, installing, testing & commission of distribution board with following : (for UPS units)**	NOS	1		
	A) Incoming : 40 A DP MCB - 2no.				
	B) Outgoing : 10/16 A SP MCB - 15 nos.				
	C) MCB & DB Make : Legrand				
5.5	**Supplying, installing, testing & commission of distribution board with following : (for UPS INPUT & OUTPUT)**	NOS	1		
	A) Incoming : 40 A DP MCB-1no.				
	B) Outgoing :- 40 A DP MCB-1no.				
	C) MCB & DB Make : Legrand				

5.6	**Supplying, installing, testing & commission of distribution board with following : (for ROW POWER)**	NOS	1		
	A) Incoming : 40 A DP MCB-2no.				
	B) Outgoing : 10/16 A SP MCB - 13 nos.				
	C) MCB & DB Make : Legrand				
6.0	**Intercom Telephone**				
6.1	**Telephone point**	NOS	26		
	A) Supply and laying of 2 pair telephone wire ISI marked PVC Insulated 0.63m sq mm. Copper conductor wire same as clause No. 1 of internal wiring from EPBEX to the various tables as per the requirement complete with RJ - 11 type Tel. Socket. all respect as per the drawing an Architect or consultant. Cross Ferruling need to be provided for each point. on Telephone point tagging must be done.				
	B) TELEPHONE Wire: Delton B				
	C) RJ - 11 type Tel. Socket : Legrand (Mylink)				
	D) PVC Conduit & Accessories Make : Polycab				
6.2	**10 pair telephone wire point**	NOS	2		
	A) Supply and laying of 10 pair telephone wire ISI marked PVC Insulated 0.63m sq mm. Copper conductor wire same as clause No. 1 of internal wiring from BSNL DP to 10 pair Krone Box as per the requirement complete including with 10 Pair Krone Box all respect as per the drawing an Architect or consultant.				
	B) TELEPHONE Wire: Delton B				
6.3	**EPABX Complete System**	NOS	1		
	A) Supplying & erecting Digital / PCM / TDM EPABX System having SMT design, system with flexible universal slots, Inbuilt Auto attendant facility, Minimum 15 Nos. conference, Analog extension line, Calling GSM, E&M line, PRI / E1 & VOIP program me through Analog telephone digital key from Ethernet, public address cord, shall have unrestricted simultaneous dialling facility, QSIG protocol on PRI, 95 / STD / ISD / Local- Locking ,Class of Service, Quick Dial-Single Digit dialling of any two external numbers, Once only ring device, Boss/Secretary- Do not Disturb Facility, Power Down Mode, Hot Line, Hot Outward Dialling, Day Night Mode, Auto Call Back, Barge-in, Call Pick Up & Call Transfer, Call transfer while Ringing. With Voice Guide System, (DISA), Caller ID (CLI), CLI Base ECF,CLI Base routing Internet Ready Port, External Music Port, Call Budgeting, Call Most Calculation(ASMDR), DID Direct Inverse Dialling, External Music Input, Fax Homing, Global Directory Printing. with following capacities				
	B) No of Extension 24, No of Junctions 8, No of expandable ports:96, Operators Console - 01 Compatible: ISDN				
	C) EPBX Make :- Matrix				

7.0	**Lan/Structure Cabling Work**				
7.1	**Lan Cable Point**	NOS	48		
	A) Supply and laying of 4 PAIR UTP LAN cable - CAT-6 e in underground /wall in 1.5mm thick PVC pipe of 25mm dia with proper junction box for maintenance purpose from Rack/server room to each work station including supply and installation at CAT -6 e information outlet with fore plate and surface/concealed box. **(One for LCD One for IP phone facility in cabin. Dual RJ45 I/O point in Single plate not allowed. Cross Ferruling need to be provided for each point. on Data point tagging must be done.**				
	B) CAT 6 Data Cable : DIGILINK / D-LINK				
	C) I/O and Face Plate : DIGILINK / D-LINK				
7.2	**Patch cord 1 mtr. Long (factory built)**	NOS	48		
	A) Supply & testing at patch cord (CAT 6e) Length 1 Meter (CAT 6e) original factory made (Connect with Patch Panel to Network Switch in Rack)				
	B) CAT 6 Data Patch Cord Make: DIGILINK / D-LINK				
7.3	**Patch cord 2 mtr. Long (factory built)**	NOS	48		
	A) Supply & testing at patch cord (CAT 6e) Length 2 Meter (CAT 6e) original factory made (Connect with Patch Panel to Network Switch in Rack)				
	B) CAT 6 Data Patch Cord Make: DIGILINK / D-LINK				
7.4	**9U Network Rack**	NOS	1		
	A) Supply, installation & testing of 9 U Network Rack with 1 fan & having one shelf in the rack with hardware etc.				
	B) Rack Make: ELIXIER / APW / RITTAL / ALFA				
7.5	**24 Port Patch Panel**	NOS	2		
	Supply & testing of 24 port patch panel CAT 6 Patch Panel.				
	B) CAT 6 Patch Panel Make: DIGILINK / D-LINK				
7.6	Testing and connection of patch panel / switch / router and modem etc.	NOS	1		
7.7	Supply and Fixing of HDMI cable with terminal if required on site	R.MT	30		
7.8	SITC of CABLE TV RG - 6 cable line in PVC Conduit pipe with proper fixing and connecting with modular Co-Axial TV Socket	R.MT	50		
8.0	**INVERTOR SYSTEM**	NOS	1		
8.1	Supply and Installing Home ups 2000 va/ 24 v dc pure sinewave with digital display with manual bypass switch with two year warranty				
	A) Make: Luminoius				
8.2	Supply and Installing battery tall tubular with 36+36=72 month warranty	Nos	2		
	A) Make: Luminoius				
				TOTAL OF PART 2:-	

PART :- 3 AUDIO VISUAL SYSTEM

Sr.No.	Description	Unit	Qty.	Rate	Amount
1.0	Supply, installation, testing and commissioning of the following items with necessary M.S iron frame/enclosure as necessary as per specification including cutting necessary chases in wall/floor and mending good damages,supply and fixing of all accessories, G.I bolts, nuts, washers, etc painting, earthing complete as required with other details as per enclosed specification.				
A	120 Watt PA system with control desk comprising 3nos. of microphone with press to talk switch and stand (Ahuja Make PRO-3200) , selector switch, mixing amplifier 120-130 watt(AHUJA MakeSSB-120 DP), Digital player: MP3 player with USB Reader & Remotecontrol cables with sockets, interconnections, earthing complete asrequired. **Make: Ahuja/Boss**	SET	1		
2.0	External speaker **8 watt unit (AHUJA MAKE: CS-6081 T**) in finished enclosure suitable for wall/ceiling mounting with external colour matching as per the final finish of the room wall/ceiling as required and having the following ratings.including Providing and laying Speaker wiring **2 nos x 1.0 Sqmm Copper wiring** in rigid PVC conduit for Speaker. Including installation testing and commissioning of speaker Wiring from PA system Amplifier (4 pionts in one circuit) **Make:Ahuja/Boss (6" dia speaker).**	NOS	4		
3.0	Providing and fixing in position the following G.I. flexible conduits including all accessories				
A	1.6 mm wall thickness 20 mm dia	R.MT	100		
4.0	9U Equipment Rack complete with mounting unit, speaker, power supply control etc. President make suitable for 1x70 watts amplifier system With all terminating set up.	NOS	1		
5.0	Supply, Installation, Testing, Commisioning of volume control - cum - ON - OFF switch flush mounted on wall along with other electrical switches .The size and plate of the regulating knob should match with other switches nearby.	NOS	4		
6.0	**LG ULTRA HD SMART LED TV :-** Supplying providing and installing of LG 139cm (55 inches) 4k Ultra HD Smart NanoCell TV 55NANO73SQA (Ashed Blue)	NOS	1		
	A) Special Feature :- Built-in Google Assistant & Amazon Alexa | Apple Airplay & Homekit | WebOS 22 with User Profiles | α5 Gen5 AI Processor 4K | AI Brightness Control, 4K Upscaling & AI Sound Pro (Virtual Surround 5.1.2 up-mix) | Filmmaker Mode, HDR 10 Pro & HLG | Game Optimizer, ALLM, HGIG Mode				
	B) Components :- 1 NanoCell 4K TV, 1 Table Top Stand, 1 User Manual, 1 Warranty Card, 1 Remote Control, 2 Batteries				
	C) Connectivity Technology :- Bluetooth, Wi-Fi, USB, HDMI				
	D) Product Dimension :- 23.2D x 123.5W x 77.4H Centimeters				
	E) Supported Internet Services :- Netflix, Prime Video, Zee5, Voot, SonyLIV, Discovery+, Youtube, YuppTV, Apple TV, Disney+ Hotstar				
				TOTAL OF PART 3:-	

PART :- 4 AIRCONDITIONING WORK

Sr.No.	Description	Unit	Qty.	Rate	Amount
1.0	**1.5 TR CAPACITY HI-WALL SPLIT AC**	NOS	3		
	A) Supply, Installation, Testing & Commissioning of 1.5 TR capacity Single Phase, minimum 5 -Star rated Inverter Hi-wall Split AC with all copper condenser & evaporator coils and with cordless remote-control including cost of copper piping upto 3 metre. Piping to be laid through insulating sleeve with white taping and to be clamped neatly. The above cost includes the stabilizer and MS stand.				
	B) MAKE :- Panasonic,O general,Mistibushi,Blue star,Hitachi				
2.0	**2.0 TR CAPACITY INVERTER CASSETTE AC**	NOS	6		
	A) Supply, Installation, Testing and commissioning (SITC) of Single-Phase INVERTER Cassette (Ceiling mounted IDU) Air conditioners with all fixing accessories, first fill of eco-friendly refrigerant (R32 or R410a) complete. Piping to be laid through nitrile rubber sleeve with white taping and to be clamped neatly. Wall openings are to be sealed and finished using cement plastering.2.0TR, capacity Inverter Cassette AC- single phase with scroll/rotary/swing Compressor (Banking Hall) (Excluding cost of copper piping). The cost of work also includes the supply and installation of ready made powder coated MS stand/angle heavy duty support for Cassette AC outdoor units (Panasonic, O general, Blue star, Hitachi)				
	B) MAKE :- Panasonic,O general, Blue star,Hitachi				
3.0	Supply & erection of copper refrigeration pipe (as specified by the manufacturer) complete with elbows, bends, supports, Insulation etc. interconnecting indoor and outdoor units(both suction and discharge lines) along with necessary Insulation using 4mm thick nitrile rubber sleeve with teflon taping for single phase split AC 1.5 Tr **(copper pipe concealed in inside wall)**	MTRS	40		
4.0	Supply & erection of copper refrigeration pipe (as specified by the manufacturer) complete with elbows, bends, supports, Insulation etc. interconnecting indoor and outdoor units(both suction and discharge lines) along with necessary Insulation using 4mm thick nitrile rubber sleeve with teflon taping for single phase cassette AC 2.0 Tr	MTRS	80		
5.0	Additional electrical wiring between indoor and out door units with all necessary fittings and leak proof arrangements as required for Split AC's of 1.5TR	MTRS	40		
6.0	Additional electrical wiring between indoor and out door units with all necessary fittings and leak proof arrangements as required for Cassette AC's of 2.0TR	MTRS	80		
7.0	Providing, installing, fixing in wall M.S. Angle Stands for Outdoor Units having capacity of 1.0/1.5 TR Hi wall inverter split AC at any level as directed by Authority.	NOS	9		
8.0	Trenching / Civil Work	JOB	1		
9.0	Providing, installing, concealed fixing in wall or through floor 25 mm Rigid PVC Drain Pipe connected to Hi wall inverter split AC as directed by Authority.	MTRS	50		
				TOTAL OF PART 4:-	
				TOTAL OF PART 1+2+3+4:-	
				We will executed work ____ % Above / Below this Above Amount :-	
				NET TENDER AMOUNT:-	
Tender Amount (In Words) Rupees:					

SIGNATURE OF TENDERER/FIRM) **(SEAL OF FIRM)**

DATE:

NAME OF TENDERER :- **PLACE:**

NOTES:

1	ALL RATES SHOULD BE INCLUDE OF ALL TAXES EXCLUDING GOOD AND SERVICE TAX (GST)
2	THE CONTRACTOR SHOULD DEPUTE ONE PERSON AT SITE FROM START OF WORK TO FINISH FOR GIVING TEMPORARY CONNECTIONS & ATTENDING PROBLEMS
3	THE CONTRACTOR SHOULD WORK ACCORDING TO THE FINAL LAYOUT.
4	THE CONTRACTOR'S PRESENCE MUST BE COMPULSORY FOR SHIFTING / INSTALLING OF UPS, DATA RACK, EPABX SYSTEMS. - MUST HELP TO BANK'S VENDORS LIKE PCS (HARDWARE), UPS, DATACRAFT (PORT SWITCH - SOFTWARE), ETC.
5	USING EXISTING PVC CONDUITS LAID IN FLOOR /WALL FOR DATA CABLES/TELEPHONE CABLES/COMPUTER POWER /RAW POWER WORK