



**TENDER FOR
INTERIOR DECORATION AND FURNISHING WORK
OF
BANK OF BARODA
KOIRA BRANCH**

CONSULTANT

Soubhagya Nayak Associates

Plot No-736, Sector-3, Niladrivihar, Chandrasekharpur, Bhubaneswar-21

Mobile - 9348779922

**BOQ FOR INTERIOR DECORATION AND FURNISHING OF BRANCH PREMISES OF
BANK OF BARODA , KOIRA BRANCH**

Sl.No.	Particulars	Unit	Quantity	Rate (in Rs.)	Amount (in Rs.)
1A	Full Height Partition (Semi Glazed)				
	Removing existing partition and applying Anti Termite treatment with approved chemicals to entire floor area & wall area (The Vendor need to produce Warranty Certificate of 5 years) after the work completion. and Providing and fixing in position partly glazed full Height Partition work as per drawing in frame work at 600 mmX600 mm grid (horizontally and vertically) comprising of 50 mm X50 mm Aluminium section of heavy gage as per frame work shown in the drawings with 12 mm BWP Grade Solid Ply (AUSTIN-GOLD/SABURI-GOLD) on both sides finished with 1.0 mm thick laminates of (SUNMICA/MERINO/SONEAR) approved shade and colour as shown in drawings. Item to include 12 mm thick Toughened glass with approved colour etching and frosting as per design and 2"x2" T.W. member for door sides and glass sides and T.W. door frame to take 12 mm thick glass with etching and frosting. All exposed T.W. surfaces to be finished in melamine polish of matching laminate colour as directed including all necessary Stainless Steel finish fittings/hardware, wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/Bank complete in all respects.(Note : In case of false ceiling, the vertical members to be fixed with pucca ceiling but the area of partition payable will be below the false ceiling only)	SFT	250.00		
1B	Full Height Partition (Fully Solid)				
	Specification same as 1(a)	SFT	150.00		
1C	Low height partition (up to 1500 mm ht.)				
	Specification same as 1(a)	SFT	100.00		
1D	Fully Glazed Partition				
	Providing , fitting & fixing 12mm thick Toughened glass partition with chemically eaching as per design.the partiton will be supported with S.S patch panel fittings asper drawing and design. The exposed edge of the glass partition should be polished to super quality. The work should be completed as perdirection of architect including cost of all labour & material	SFT	100.00		
1E	Pine Wood Beading				
	Providing,fitting and fixing Pine wood beading in low height partion,cash counter front & low height cash counter front with All Pine wood beading surfaces to be finished in melamine polish of matching laminate colour as directed.The work should be completed as per direction of architect including cost of labour and material	RFT	100.00		

Sl.No.	Particulars	Unit	Quantity	Rate (in Rs.)	Amount (in Rs.)
2A	Doors (Semi Glazed)				
	Removing existing partition and applying Anti Termite treatment with approved chemicals to entire floor area & wall area (The Vendor need to produce Warranty Certificate of 5 years) after the work completion. and Providing and fixing in position partly glazed full Height Partition work as per drawing in frame work at 600 mmX600 mm grid (horizontally and vertically) comprising of 50 mm X50 mm Aluminium section of heavy gage as per frame work shown in the drawings with 12 mm BWP Grade Solid Ply (AUSTIN-GOLD/SABURI-GOLD) on both sides finished with 1.0 mm thick laminates of (SUNMICA/MERINO/SONEAR) approved shade and colour as shown in drawings. Item to include 12 mm thick Toughened glass with approved colour etching and frosting as per design and 2"x2" T.W. member for door sides and glass sides and T.W. door frame to take 12 mm thick glass with etching and frosting. All exposed T.W. surfaces to be finished in melamine polish of matching laminate colour as directed including all necessary Stainless Steel finish fittings/hardware, wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/Bank complete in all respects.(Note : In case of false ceiling, the vertical members to be fixed with pucca ceiling but the area of partition payable will be below the false ceiling only)	SFT	170.00		
2B	Flap Door (up to 1.5 M. ht)				
	Specification same as 2A , but fully solid	SFT	15.00		
2C	Main Entrance Door (With Toughened Glass)				
	Providing and fixing fully glazed Aluminium (heavy duty 14 gauge)Doors at the Main Entrance with 6"x2" sections for top & bottom rails, 2"x2" for vertical styles.12mm thk toughened glass with frosting and etching/LOGO shall be fixed in the framing.Rate shall include pad lock,heavy duty floor spring (2 nos),18"long S.S Handles (2 nos),gaskets,top and bottom patch fitting locking systems of approved make.	SFT	50.00		
3	Door Closer				
	Providing and fixing Godrej make over head door closers to manager's chamber door with necessary fixtures and fittings etc.	NOS	5.00		
4	Floor Spring				
	Providing & fixing Godrej make heavyduty floor spring in entrance door with necessary fixtures and fittings etc.	NOS	1.00		
5	False ceiling (With Tray & Drop)				

Sl.No.	Particulars	Unit	Quantity	Rate (in Rs.)	Amount (in Rs.)
	False Ceiling (Gypsum Board)Providing & fixing in position false ceiling in Gypboard 12 mm thick (with 3" cornice) for horizontals & Verticals fixed over G.I. frame workas specified by India Gupsm Co. Ltd. including trap doors for A.C. Unit in 18mm thick M. R. Grade Plywood with Stainless Steel hinges & locks with moulding 1" x 1" for edges including finishing with White Plastic Emulsion Paint etc. complete in all respects.(Note :- Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves,mouldings etc.)	SFT	800.00		

Sl.No.	Particulars	Unit	Quantity	Rate (in Rs.)	Amount (in Rs.)
6	Modular False Ceiling				
	Providing & fixing in position false ceiling in Armstrong 600 x 600 mm x 15/16 mm Dune Supreme RH 95 Prima tile with sheihard gride Tegularedge framework as specified by Armstrong Co. with suspenders whereverrequired. Making necessary framework for A. C. ducting, if any, andnecessary cutouts for diffusers and light fittings, taping and finishing toproper line & level, including making grooves and trap doors for A. C. unit in18 mm thick M. R. Grade Plywood with Stainless Steel hinges & locks withmoulding 1" x 1" for edges including finishing with White Plastic Emulsion Paint etc. complete in all respects.(Note :- Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves,mouldings etc.)	SFT	200.00		
7	Front Office Counter.				
	Providing and fixing of front office counter table size of 5'-6"X3'0"x2'-6" with Modular Table Top of 25 mm thick Ply Board and consist drawer units slides on telescopic slider and a cupboard unit made-up of 19 mm thick ply with locking arrangement. The unit also include a 4" front edge band . The exposed edge surfaces are to be finished with 1.0 mm thick laminates as per design of approved shade and the inner surface is finished with 0.8 mm thick laminate of approved shade . A cable manager is to be fixed as per drawing and design. The work is to be completed with all labour and material including all the hardware required.	NOS	2.00		
8	Cash Counter				
	Providing and fixing of counter table of size 5'0"x3'-0"x 2'-6" with Modular Table Top of 25 mm thk Ply Board and the front facia israised up to ht of 3'-10" and front drawer unit consisting 3 Nos of drawerunits slides on telescopic slider made up of 19 mm thick BWP grade ply (AUSTIN-GOLD/SABURI-GOLD) ply with locking arrangement. The exposed edge surfaces are to be finished with 1.0 mm th.laminates as per design of approved shade and the inner surface to be finished with 0.8 mm thick laminate of approved shade . A cable manager is to be fixed as per drawing and design.It also include a 12 mm thick fully eached and edge polished 15" wide horizontal glass member fixed with the partition by SS patch panel and SS stude as per design. The work is to be completed with all labour and material as per drawing and design including all the hardware required.	NOS	1.00		

Sl.No.	Particulars	Unit	Quantity	Rate (in Rs.)	Amount (in Rs.)
9	Manager's Table				
	Providing modular executive type manager table top of size 5'-6"X3'-0"X2'-6",with Modular Table Top of 25 mm thk Ply with Postforming edges and a side credenza of size 3'-0"X1'-6"X2'-6" and a front drawer unit consisting 3Nos of drawer units slides on telescopic slider made up of 19 mm thk BWP grade ply (AUSTIN-GOLD/SABURI-GOLD) with locking arrangement. The exposed edge surfaces are to be finished with 1.0 mm thick laminates as per design of approved shade and the inner surface is finished with 0.8 mm thk laminate of approved shade . A cable manager is to be fixed as per drawing and design.The side credenza will have two drawer unit slides on telescopic slider and two cupboard unit. The work should be completed including all labour and material.	NOS	1.00		
10	May I Help You (8'-0" X 2'-6")				
	Providing and fixing in position May I Help You table made out of 19mm BWR BB for front , top and sides finished with 1.0mm thk. Laminate . Table will have two drawers made out of 19mm thk. BWR BB ,1.0mm laminate for front,12mm BWR ply for both sides and 6mm ply for base and shutter fabricated out of 19mm BWR BB ,1.0mm thk. Laminate. Drawer should run on Sliding channel.All inside area to be enamel painted.All exposed edges to be finished with white beach/white cedar moulding/lipping(as per design)with natural polish.Wire manager (approved colour),Ready made CPU trolley,leg rest,black powder coated readymade Key board tray, Mouse pad tray finished with 1.0mm laminate to be provided.The drawer & shutters to be provided with 4" s/s finish handle,godrej multipurpose lock,auto closing hinges etc.Table will have 12mm thk. bevelled glass and 18mm thk.jet black granite for top.19mm BWR b/b finished with 1.0mm thk.bruss steel laminate to be provided as shown in drawing.Table front will have some rasied portition finished with 1.0mm thk approved colour laminate as per drawings.The work to be completed	NOS	1.00		
	As per specification,design and approval of the Architects.				
11	Back Officer's Table				

Sl.No.	Particulars	Unit	Quantity	Rate (in Rs.)	Amount (in Rs.)
	<p>Providing and fixing of Back office counter table size of 4'-6"X2'-6"x2'-6" with Modular Table Top of 25 mm thk Ply with Postforming edges and consist drawer units slides on telescopic slider and a cupboard unit made-up of 19 mm thick BWP Grade Ply (AUSTIN-GOLD/SABURI-GOLD) with locking arrangement. The unit also include a 4" front edge band . The exposed edge surfaces are to be finished with 1.0 mm thick laminates as per design of approved shade and the inner surface is finished with 0.8 mm thick laminate of approved shade . A cable manager is to be fixed as per drawing and design. The work is to be completed with all labour and material including all the hardware required.</p>	NOS	3.00		

Sl.No.	Particulars	Unit	Quantity	Rate (in Rs.)	Amount (in Rs.)
12	Daftari Table				
	Providing & fixing of counter table of 3'-0"X2'-9" and front drawer unit consisting 3 No's of drawer units slides on telescopic slider made up of 19mm th. Ply with locking arrangement. The exposed edge surfaces are to be finished with 1.0mm th. Laminates as per design of approved shade and the inner surface is painted with two coats of enamel paint of approved colour over one coat of primer with cable manager are to be fixed as per drawing and design. The work is to be completed with all labour and material including all the hardware required.	NOS	1.00		
13	Running Table For Fax/Printer				
	Providing and fixing of running counter table with Modular Table Top made up of 25 mm thick ply with Postforming edges and drawer unit consisting 3 No's of drawer units slides on telescopic slider made up of with locking arrangement. The exposed edge surfaces are to be finished with 1.0 mm th.laminates as per design of approved shadea and the inner surface is finished with 0.8 mm thick Laminate of approved shade and colour. A readymade key board try, CPU traly (EBCOmake) and cable manager are to be fixed as per drawing and design.Thework is to be completed with all labour and material including all the hardware required.	RFT	5.00		
14	Low Height & Full Height Storage (450mm Depth)				
	Providing and fixing of low height storage cabinete having 450 mm. depth & 25 mm thk Modular Top made from 25 mm thick BWP grade Solid ply (AUSTIN-GOLD, SABURI-GOLD) all side finished with 1.0 mm thick Laminate of approved shade on the exterior side as per design of approved colour and the inner surface is finished with 0.8 mm thick Laminate of approved colour. The work shall be completed with all necessary hardwares i.e, S.S Handles,brass locks,wall catches etc,labour and materials etc.	SFT	350.00		
15	Key Board Tray				
	Providing & supplying metal keyboard tray without Mousepad manufacture by M/S Godrej/EBCO.The Keyboard is pullout type, fixed to channels and screwed to below table top.	NOS	7.00		
16	CPU Trolley				
	Providing & supplying metal CPU trolley manufactured by M/S Godrej/EBCO attached with 4 wheels for holding CPU and smooth movement.	NOS	7.00		

Sl.No.	Particulars	Unit	Quantity	Rate (in Rs.)	Amount (in Rs.)
17	Wall & Column Panelling				
	Encasing to columns , Banking hall etc where ever shown in drawings by fixing 12 mm thick BWP Grade Ply (AUSTIN-GOLD, SABURI-GOLD) and providing 6.0 mm thk horizontal grooves to the frames made out of Heavy duty Aluminium Box sections 50mmX25mm@600mm c/c,both ways horizontally and vertically on the wall by means of nailing or screwing over with 1 mm thick laminate of approved shade fixed by means of adhesive having grooves & necessary white beach beading as directed by the Architect finished with wooden moulding,skirting & Lipping etc. . At places niches shall be created to accommodate 12 mm tk soft board & fabric of approved quality fixed with necessary frame work of wood . Nitches shall be leaped with WB wood which is also melamine polished. The cost includes all the materials, labour, transportation taxes etc., complete for the work.	SFT	300.00		
18	Suggestion Box				
	Supplying and erecting free-standing suggestions box of overall size , 450 mm long x 300 mm deep x 900 mm high made of 19 mm thick phenol formaldehyde block board, all as in drawing, complete. with hardware. Fittings and fixtures of approved make and quality. Top and all exposed surfaces of block board are to be finished with 1mm thick laminate sheet of approved shade and quality. Inner faces of block board surfaces are to be finished with minimum two coats of synthetic enamel paint of approved shads and quality over a coat of approved primer.	NOS	1.00		
19	Cheque Drop Box				
	Supplying and erecting cheque drop box (overall size 450 mm x 300 mm x 750 mm) made. of 19mm thick phenol formaldehyde bonded plyboard andhe curved portion at top made out of 90 mm x 90 mm C.Pteak woodsection. A slit opening of 10 mm x 150 mm is to be provided at the top of thebox. An openable shutter of 259 mm x 262 mm size made of 1 9 mm thickphenol formaldehyde bonded block board is to be provided at 1.50 mmabove finished floor level. All the exposed timber surfaces including. all freedges are to be finished with 1 rnm thick laminate sheet of combinationshade .Inner faces of block board surfaces are to be finished with minimumtwo coats of synthetic enoma!. paint of approved shade and quality over acoat of approved primer.Rate .to include cost of necessary hardware fittingse.g. brass hinges, lock, knob etc. of approved.designand quality.	NOS	1.00		

Sl.No.	Particulars	Unit	Quantity	Rate (in Rs.)	Amount (in Rs.)
20	Writing Platform for Customers & Application Form Set				
	Providing , fitting , fixing writing plat form at a height of 4' above floor level fixed to the wall made out of 19 mm BWP block board with lamination 1 mmtk on top & hard wood beading ducco painted . At least 10 nos vertical slip inchalan shelves attached to wall over writing platform made out of min 4 mm tkacrylic sheets with 6 mm tk ply back up. Each chalan shelf will be of size 6"height , 6" wide .The entire unit will be complete in allrespect includingmaterials ,labor etc to the satisfaction of consultant .	RFT	5.00		
21	Notice Board.				
	Providing soft board covered with approved fabric with wooden frame work and decorative beading for display drawings and documents,with lockingarrangementof the sliding shutter made up of 8mm th. flot glass. The workshould be done including all labour and material.	SFT	15.00		
22	Roller Blinds				
	Supplying, fitting & fixing in position coloured 0.33mm thickness acrylic coated cleanable/ washable Roller blinds (Marvel or its equivalent, as approved) inclusive of all recommended accessories colour pattern etc., as per Architect's approval. The cost includes all the materials, labour,transportation taxes etc., complete for the work.	SFT	50.00		
23	Wall Plastic Paint.				
	Providing & applying 2 coats of plastic emulsion paint of royale ICI dulux & approved shade on wall, columns, beams, ceiling, etc. of back office hallincluding locker room, including preparation of surface, sand papering theintermediate coats, including cost of all materials, labour, conveyance,taxes, royalties, scaffolding, watering, curing, sundries, T&P, etc., as per direction of Engineer-in-charge.	SFT	3,000.00		
24	Wall Putty Work (With P.O.P Punning)				
	Providing and applying wall puttyputty work punning in order to make the total plastered wall surface perfectly leveled , including cost of all materials,labour, conveyance, taxes, royalties, scaffolding, watering, curing, sundries,T&P, etc., as per direction of Engineer-in-charge.	SFT	1,500.00		
25	Rolling Shutter Boxing (With A.C.P)				

Sl.No.	Particulars	Unit	Quantity	Rate (in Rs.)	Amount (in Rs.)
	Providing & fixing 3 mm thick Aluminium Composite Panel boxing for existing rolling shutter.Necessary arrangement shall be provided for trap door for smooth operation of shutters and rest is closed with mirror screws.the shutter shall be finished with approved 3.0 mm thick ACP on all exposed sides, enamel paint internally and the rates shall be inclusive of all fittings like hinges, ball catches, tower bolt (Ebco make) etc	SFT	50.00		

Sl.No.	Particulars	Unit	Quantity	Rate (in Rs.)	Amount (in Rs.)
26	Banks Logo,Poster Frame,Pin Board				
	S.S logo of Bank Of Baroda in SS plate of 18 inch dia and Poster Frame - one set poster frame consisting 2 sheets of imporetd acrylic of 5 mm thickness front sheet with half inch moulding and edge polished;back sheet with polished edge and Alumunuum stud for fixing the frame on wall,One Pin Board for fixing Notices and other communication made of 24"X18" soft board,with hardwood and aluminium frame,covered with satin of appropriate colour.	NOS	6.00		
27	Softscape Elements				
	Providing rectangular Landscape boxes of size in Main Entrance area ,in pot shaped boxing and finishing using 1.0 mm thick stainless steel finish mica of ISI Grade and edges finished in hardwood reapers all around and filling a height of 8" width ,filling with white pebbles of 1/2" to3/4" size and inserting 4 nos indoor plants and green creepers.The size of plywood boxing has to be 5'0"X1'3" and height 1'6" using 19 mm marine ply boxing.The rate shall include materials,labour,fitting and fixing etc complete and as per the direction of the Architect/Bank.	NOS	2.00		
28	Banks Signage At Main Entry				
	Providing and fixing Digital type Internal signage of size (3'0"X5'0") with acrylic sheet,on both sides of the Main Entrance including the logo of BANK OF BARODA in exposing Digital Letter of approved size including lighting with LED strips/LED Tube ,with necessary aluminium boxing ,26 gauge G.I Sheet at the back with LDR based timer of kakatia energy system or G.E/L&T make.The rate includes the cost of material,labourcharges and fixing etc.	SFT	15.00		
29	Shutters With Frame For Electrical Panel				
	Providing and fixing 18mm thk. Com ply shutters with same ply frame. Division of shutters shall be made equally according to the length. Shutters shall be hinged to the framework and finished with 1.0mm thk. Laminate of approved colour and shade on outer side and inside finised with 2 coats of enamel paint of app colour and shade. Rate shall be inclusive of all necessary approved fittings like hinges, ball catch,150 mm long SS Brush Finish handle, tower bolts, locks, Aluminium powder coated air vent grills and necessary hardware fitings complete, etc.,	SFT	20.00		
31	Sanitary Items				

Sl.No.	Particulars	Unit	Quantity	Rate (in Rs.)	Amount (in Rs.)
A	Textured Finish Paint : Providing & applying a coat of textured finish on walls and columns. The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats of approved make, quality & shade shall be provided. Sample shall be approved by the Architect/Bank	SFT	200.00		
B	Wall papers : Providing and fitting and fixing of wall paper on wall of approved make inclusive of all cost of labour material,T&P as per the detail design and specification & as per direction of Architect . (Sample shall be approved by Architect/Bank)	SFT	200.00		
C	Water Purifier : Supply and Installation of Electric R.O Water Purifier of approved make of KENT/AQUAGUARD,8LTR capacity including plumbing work,material and labour etc complete.	NOS	1.00		

Sl.No.	Particulars	Unit	Quantity	Rate (in Rs.)	Amount (in Rs.)
30	Buyback of Old Items				
	Buyback of existing old items as per the list given by Bank.Minimum Buyback Value - 60,000.00	JOB			
	TOTAL			Rs	

--

Sl.No.	Particulars	Unit	Quantity	Rate (in Rs.)	Amount (in Rs.)
BOQ FOR INTERIOR DECORATION AND FURNISHING OF E-LOBBY OF BANK OF BARODA, KOIRA BRANCH					
Sl.No.	Particulars	Unit	Quantity	Rate (in Rs.)	Amount (in Rs.)
1A	Full Height Partition (Fully Solid)				
	Providing and fixing of full ht solid partition made out of salwood frame centre to centre section size 2"x 2" both ways rigidly fixed/covered with wooden plug/raw plug with 9 mm thk comm. ply and MS Grill (4"x4" c/c of 8 mm square bar duly painted with enamel paint and metal based primer) sandwiched between wooden frame and 9mm thk. ply to strengthen partition, finished with one side with 1.5 mm thick laminate and other side with 6mm thick extra clear white back painted glass in plumb line and level, fixed with groove, finished the joints/grooves with matching colour silicon. M.S. grill shall be fixed/grouted firmly at ground and ceiling at every 2' interval with heavy duty hold fast or as directed by bank. Rate shall be of Inclusive of P/f of silver metal coated laminates skirting of 75mm high & groove at skirting level.	SFT	50.00		
B	as Above but finished in both side laminates.				
2A	Door (Flush Door)				
	Providing & fabricating fixing door shutter with 28mm x 75mm height & 28mm x 75mm, 28 mm x 60mm, 28mm x 80mm rails respectively by using Giringa/ Kasi wood of well seasoned with necessary wood joining, planning, polishing etc., as per drawing matching the aligned partition. The shutter will have part glazed 8mm thk float glass side beveled, high polished with body itching of st globain & part solid one covered with 6mm BWP ply, both sides covered with 1 mm tk laminate of approved shade with necessary WB wood beading etc mat polished with melamine polish of asian / ici, complete to match the aligned partition elevations designs, the rates are inclusive of cost of necessary hinges, handles, Godrej make nightlatch, hydraulic door Closure, aldrops etc., all labour, materials, taxes, leads & lift to the place of work executed to the satisfaction of the Architect.	SFT	18.00		
2B	Main Entrance Door. (Size - 3'6"X7'0")				

Sl.No.	Particulars	Unit	Quantity	Rate (in Rs.)	Amount (in Rs.)
	Providing , fitting and fixing Entrance Door (Glazed) as per drawing in red Anodised aluminium door single groove section of size 125mmx25mm (Jindal make) in top and bottom & side glazed with 12mm thick glass of approved make with etching and frosting. Item to include all necessary hardware of Stainless Steel finish as approved by Project Consultant/Bank complete in all respects.8mm thick glass door Corporation bank monogram in itching pattern.and Door mat of approved size as per the site requirements.	SFT			
	(a) Open able portion (with Banks Monogram and handle)	SFT	25.00		
	(b) Fixed portion				

Sl.No.	Particulars	Unit	Quantity	Rate (in Rs.)	Amount (in Rs.)
3	FRONT GLAZING				
	Providing and fixing of fully glazed partition with 12mm thick toughened glass fitted with heavy duty SS patch fittings at the interval of minimum 2' interval at top, bottom and sides as per site condition.	SFT	80.00		
4A	CHEQUE DROP BOX				
	Providing and making cheque drop box 1.5'x1'x(9" deep)as per design & pattern with 19 mm ply finished exterior surface with 6 mm thick extra clear white painted glass having 4"x1" slots with 3 mm thick S.S. plat pasted with metal adhesive. Rate shall includes all necessary hardwires and locking and side opening arrangements.	NOS	1.00		
B	as above but for 6" deep dustbins having 4"xas per design & pattern.				
5A	Glass Divider:				
B	Providing and fixing of 12 mm thick toughened frosted glass divider between machines with necessary fittings and hardware as per drawing	SFT	50.00		
C	Providing cylindrical type SS dustbin of 9" dia & 18" height	NOS	2.00		
D	P& F OF 3'X2' aluminum signage with double layer 5mm thk. Acrylic sheet fixed with SS Stud as per design and pattern provided by Bank.	NOS	2.00		
6A	Writing Ledge				
	One nos of writing ledge cum information panel and storage space made of 16swg ms steel,powder coated with asian paint powder finish with PU coating and scratch resistance and UV protection.SET should be painted with logo colour.Cheque drop box in an integrated design and collapsible lid betwvwn yhe cheque drop box outlet and waist bin to avert instance of cheque being dropped accidentally in the waste bin while being collected.	NOS	1.00		
B	Providing and making cantilever ledge rested on two nos. cheque drop box at 3'6" height of size as per desing in curve shape at vertical & horizontal junctions using 6mm flexible ply finished with high gloss laminates of matching shade laminates.		NIL		
7	Banks Logo,Poster Frame,Pin Board				
	S.S logo of Bank Of Baroda in SS plate of 18 inch dia and Poster Frame - one set poster frame consisting 2 sheets of imporettd acrylic of 5 mm thickness front sheet with half inch moulding and edge polished;back sheet with polished edge and Alumunuum stud for fixing the frame on wall,One Pin Board for fixing Notices and other communication made of 24"x18" soft board,with hardwood and aluminium frame,covered with satin of appropriate colour.	NOS	2.00		

Sl.No.	Particulars	Unit	Quantity	Rate (in Rs.)	Amount (in Rs.)
8	Floor Spring				
	Providing & fixing Godrej make heavyduty floor spring in entrance door with necessary fixtures and fittings etc.	NOS	1.00		
9	False ceiling				
	False Ceiling (Gypsum Board) Providing & fixing in position false ceiling in Gypboard 12 mm thick for horizontals & Verticals fixed over G.I. frame workas specified by India Gypsum Co. Ltd. including trap doors for A.C. Unit in 18mm thick M. R. Grade Plywood with Stainless Steel hinges & locks withmoulding 1" x 1" for edges including finishing with White Plastic EmulsionPaint etc. complete in all respects.(Note :- Only the plan area will bemeasured for payment. No extra payment will be made for cutouts, grooves,mouldings etc.)	SFT	200.00		
10	Flower Pot				
	Flower Pot made of BRASS with asortment of artificial flower plants of premium quality as per the drawing laid down by the Architect.	NOS	1.00		
11	Fire Extinguisher				
	Providing 1Kg capacity "ABC" type fire Extinguisher	NOS	1.00		
12A	Wall Panelling (With ACP)				
B	Providing & Fixing in position aluminum composite panel (ACP) with framing of aluminium tube sections of min 1.5"-1" and 20 gauge 2'-0" C/C both ways. ACP to be in 2' width panels or distributed equally.Panel to be fixed to the frame with 3M or equivalent adhesive.Joint to be finished with silicon based sealant. ACP thickness of 3 mm minimun.Aluminium foil thickness to be Min 0.20MM both sides.ALUBOND,EUROBOND,or equivalent ISO certified or approved brands to be used.	SFT	350.00		
13	Wall Plastic Paint.				
	Providing & applying 2 coats of plastic emulsion paint of royale ICI dulux & approved shade on wall, columns, beams, ceiling, etc. of back office hallincluding locker room, including preparation of surface, sand papering theintermediate coats, including cost of all materials, labour, conveyance,taxes, royalties, scaffolding, watering, curing, sundries, T&P, etc., as per direction of Engineer-in-charge.	SFT	NIL		
14	Wall Putty Work.				
	Providing and applying wall putty work punning in order to make the total plastered wall surface perfectly leveled , including cost of all materials,labour, conveyance, taxes, royalties, scaffolding, watering, curing, sundries,T&P, etc., as per direction of Engineer-in-charge.	SFT	NIL		

Sl.No.	Particulars	Unit	Quantity	Rate (in Rs.)	Amount (in Rs.)
15	Wall Panelling (With Laminate)				
	Encasing to columns , Banking hall etc where ever shown in drawings by fixing 12.0 mm thick BWR Grade Ply (Duro,Mayur Gold) and providing 6.0 mm thk horizontal grooves to the frames made out of Heavy duty Aluminium Box sections 50mmX25mm@600mm c/c,both ways horizontally and vertically on the wall by means of nailing or screwing over with 1 mm thick laminate of approved shade fixed by means of adhesive having grooves & necessary white beach beading as directed by the Architect finished with wooden moulding,skirting & Lipping etc. . At places niches shall be created to accommodate 12 mm tk soft board & fabric of approved quality fixed with necessary frame work of wood . Nitches shall be leaped with WB wood which is also melamine polished. The cost includes all the materials, labour, transportation taxes etc., complete for the work.	SFT	NIL		
16	Rolling Shutter Boxing (With A.C.P)				
	Providing & fixing 3 mm thick Aluminium Composite Panel boxing for existing rolling shutter.Necessary arrangement shall be provided for trap door for smooth operation of shutters and rest is closed with mirror screws.the shutter shall be finished with approved 3.0 mm thick ACP on all exposed sides, enamel paint internally and the rates shall be inclusive of all fittings lke hinges,ball catches,tower bolt (Ebco make) etc	SFT	150.00		
17	Granite Cladding				
	Providing and fixing 1" thick granite slab of approved quality & shade for floor and wall as per approved pattern and according to specified sizes . The rate shall include machine polishing the edges, necessary backing material, water proofing and joint filling compound of the same shade as that of the granite slab.	SFT			
TOTAL				Rs	

ABSTRACT

INTERIOR DECORATION AND FURNISHING WORK OF BRANCH	Rs	
INTERIOR DECORATION AND FURNISHING WORK OF E-LOBBY	Rs	
GRAND TOTAL		
Total Amount in words - Rupees (Excluding GST)		